


I HEREBY CERTIFY THAT THIS ENGINEERING DOCUMENT DESCRIBED BELOW WAS PREPARED BY ME OR UNDER MY DIRECT PERSONAL SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF IOWA.

JAMES CARROLL Printed or typed name:

My License Renewal Date is: DECEMBER 31, 2023

F.W. KENT PARK DUMP STATION

JOHNSON COUNTY CONSERVATION BOARD 2048 HIGHWAY 6 NW OXFORD, IOWA 52322



JOHNSON COUNTY

Ν	
PROJECT LOCA	TION
NOT TO SCALE	

THE 2023 EDITION OF THE IOWA STATEWIDE URBAN STANDARD SPECIFICATIONS (SUDAS), PLUS GENERAL SUPPLEMENTAL SPECIFICATIONS, AND APPLICABLE SUPPLEMENTAL SPECIFICATIONS, DEVELOPMENTAL SPECIFICATIONS, AND SPECIAL PROVISIONS SHALL APPLY TO ALL WORK PERFORMED ON THIS PROJECT

Sheet List Table			
Sheet Number	Sheet Title		
C000	COVER SHEET		
C001	QUANTITIES & NOTES		
CD01	EXISTING CONDITIONS & REMOVAL PLAN		
C100	OVERALL SITE PLAN		
C101	SWPPP		
C102	DUMP STATION PLAN		
C103	SOIL BED AREA PLAN		
C201	SOIL BED GRADING PLAN		
C301	DUMP STATION & SEPTIC SYSTEM PLAN & PROFILE		
C501	DETAILS		
C502	DETAILS		
C503	DETAILS		

CERTIFICATIONS:

CIVIL ENGINEER

I HEREBY CERTIFY THAT THIS ENGINEERING DOCUMENT DESCRIBED BELOW WAS PREPARED BY ME OR UNDER MY DIRECT PERSONAL SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF IOWA.

Dan Jensen

5-31-2023

5-31-2023

DANIEL JENSEN Printed or typed name: 25063 License Number:

My License Renewal Date is: DECEMBER 31, 2023

PAGES, SHEETS OR DIVISIONS COVERED BY THIS SEAL: C000, C001, CD01, C100, C101, C201, C501, C503.

SEPTIC SYSTEM ENGINEER



11328 License Number:

PAGES, SHEETS OR DIVISIONS COVERED BY THIS SEAL: C102, C103, C201, C301, C502.

GENERAL NOTES

- 1. UTILITY NOTE:
- A. THE LOCATIONS OF UTILITY MAINS, STRUCTURES AND SERVICE CONNECTIONS PLOTTED ON THIS DRAWING ARE APPROXIMATE ONLY AND WERE OBTAINED FROM RECORDS MADE AVAILABLE TO SHIVE-HATTERY, INC. THERE MAY BE OTHER EXISTING UTILITY MAINS, STRUCTURES AND SERVICE CONNECTIONS NOT KNOWN TO SHIVE-HATTERY, INC. AND NOT SHOWN ON THIS DRAWING. THE VERIFICATION OF EXISTENCE OF, AND THE DETERMINATION OF THE EXACT LOCATION OF, UTILITY MAINS, STRUCTURES AND SERVICE CONNECTIONS SHALL BE THE RESPONSIBILITY OF THE CONSTRUCTION CONTRACTOR(S).
- 2. NOTIFY UTILITY COMPANIES WHOSE FACILITIES ARE SHOWN ON THE PLANS OR KNOWN TO BE WITHIN CONSTRUCTION LIMITS OF THE SCHEDULE PRIOR TO EACH STAGE OF CONSTRUCTION.
- 3. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL UNCOVER EXISTING UTILITIES AT CRITICAL LOCATIONS TO VERIFY EXACT HORIZONTAL AND VERTICAL LOCATION.
- 4. IOWA CODE 480, UNDERGROUND FACILITIES INFORMATION, REQUIRES VERBAL NOTICE TO IOWA ONE-CALL 1-800-292-8989, NOT LESS THAN 48 HOURS BEFORE EXCAVATING, EXCLUDING WEEKENDS AND HOLIDAYS.
- 5. NOTIFY THE APPROPRIATE GOVERNING AUTHORITY 48 72 HOURS PRIOR TO BEGINNING CONSTRUCTION WITHIN PUBLIC RIGHT-OF-WAY. JOHNSON COUNTY CONSERVATION SHALL BE THE PUBLIC AGENCY RESPONSIBLE FOR INSPECTION DURING CONSTRUCTION OF THE PUBLIC PORTIONS OF THE PROJECT.
- 6. THE MEANS OF THE WORK AND THE SAFETY OF THE CONTRACTOR'S EMPLOYEES ARE SOLELY THE RESPONSIBILITY OF THE CONTRACTOR.
- 7. NO WORK SHALL BE PERFORMED BEYOND THE PROJECT LIMITS WITHOUT PRIOR AUTHORIZATION FROM THE OWNER'S REPRESENTATIVE.
- 8. A PRE-CONSTRUCTION MEETING SHALL BE HELD FOLLOWING ISSUANCE OF THE NOTICE TO PROCEED BUT PRIOR TO COMMENCING WORK.
- 9. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE 2023 EDITION OF THE IOWA STATEWIDE URBAN STANDARD SPECIFICATIONS
- (SUDAS), UNLESS OTHERWISE NOTED ON THE DRAWINGS.

 10. PROVIDE TRAFFIC AND PEDESTRIAN CONTROL MEASURES (SIGNS, BARRICADES, FLAGGERS, ETC.) IN COMPLIANCE WITH PART VI OF THE
- 11. PROTECT EXISTING UTILITIES DURING CONSTRUCTION.
- 12. MAINTAIN POSITIVE DRAINAGE ON THE SITE THROUGHOUT THE PROJECT DURATION.

MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) LATEST EDITION.

- 13. ADJUST ALL VALVES, MANHOLES, CASTINGS, GAS VENTS, ETC., TO MATCH THE NEW SURFACE. ADJUSTMENT SHALL BE COORDINATED WITH THE UTILITY COMPANIES AND THE COST FOR ALL ADJUSTMENTS SHALL BE INCIDENTAL TO THE CONSTRUCTION. AT NO ADDITIONAL COST TO THE OWNER, REPAIR ANY DAMAGE TO SAID STRUCTURES AND APPURTENANCES THAT OCCUR DURING CONSTRUCTION.
- 14. SITE CLEAN-UP SHALL BE PERFORMED ON A DAILY BASIS. SIDEWALKS, PARKING LOTS, ROADWAYS, ETC. SHALL BE KEPT CLEAN AT ALL TIMES
- 15. ALL OPEN EXCAVATIONS SHALL BE PROTECTED.
- 16. REPLACE ANY PROPERTY MONUMENTS REMOVED OR DESTROYED BY CONSTRUCTION. MONUMENTS SHALL BE SET BY A LAND SURVEYOR REGISTERED TO PRACTICE IN THE STATE OF IOWA.
- 17. CONSTRUCTION ACTIVITIES ARE TO BE LIMITED TO THE EXTENTS SHOWN ON THE PLANS. IF ADDITIONAL AREAS ARE NEEDED FOR STAGING, STORAGE, ETC., IT IS THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN WRITTEN PERMISSION FROM THE PROPERTY OWNER(S). COPIES OF THE AGREEMENTS SHALL BE SUBMITTED TO THE OWNER'S REPRESENTATIVE PRIOR TO THE USE OF PROPERTY.
- 18. CONTROL DUST SPREADING FROM ALL WORK AND STAGING AREAS.
- 19. ANY WORK REQUIRED TO COMPLETE THE SCOPE OF THIS PROJECT BUT NOT SET FORTH AS A SPECIFIC BID ITEM, SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT. NO ADDITIONAL COMPENSATION SHALL BE ALLOWED FOR THE COMPLETION OF THIS WORK.
- 20. REPAIR OR REPLACE EXISTING FACILITIES (CURBS, PAVEMENT, UTILITIES, ETC.) TO REMAIN, AT NO ADDITIONAL EXPENSE TO THE OWNER.
- 21. IT IS INTENDED THAT ALL COSTS OF MATERIALS, EQUIPMENT, TOOLS, LABOR AND INCIDENTALS BE PAID FOR UNDER THE ITEMS LISTED ON THE BIDDER'S PROPOSAL. BEFORE SUBMITTING A BID ON THIS PROJECT, THE CONTRACTOR SHALL EXAMINE ALL DRAWINGS, SPECIFICATIONS, SPECIAL PROVISIONS AND THE JOB SITE. IF ANY DISCREPANCIES OR DELETIONS OCCUR IN THE CONTRACT DOCUMENTS, THE CONTRACTOR SHALL REPORT SAME TO SHIVE-HATTERY, INC. IN WRITING AND OBTAIN WRITTEN CLARIFICATION AND/OR INSTRUCTIONS ON HOW TO PROCEED.
- 22. WORK WHICH DOES NOT CONFORM TO THE REQUIREMENTS OF THE CONTRACT WILL BE CONSIDERED UNACCEPTABLE. UNACCEPTABLE WORK, WHETHER THE RESULT OF POOR WORKMANSHIP, USE OF DEFECTIVE MATERIALS, DAMAGE THROUGH CARELESSNESS OR ANY OTHER CAUSE, FOUND TO EXIST PRIOR TO THE FINAL ACCEPTANCE OF THE WORK, SHALL BE REMOVED AND REPLACED IN AN ACCEPTABLE MANNER, AS REQUIRED BY SHIVE-HATTERY, INC. AT THE CONTRACTOR'S EXPENSE. WORK DONE CONTRARY TO THE INSTRUCTIONS OF SHIVE-HATTERY, INC., WORK DONE BEYOND THE LINES SHOWN ON THE PLANS OR ANY EXTRA WORK DONE WITHOUT AUTHORITY WILL NOT BE PAID FOR.
- 23. THE CONTRACTOR SHALL PROTECT ALL TREES SHOWN TO BE SAVED ON THE PLANS. CONTRACTOR SHALL ERECT FENCING AROUND TREE AT THE DRIP LINE, UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR PARK OR TRAVEL WITH ANY VEHICLE UNDER THE TREE DRIP LINE.

ESTIMATED PROJECT QUANTITIES

#	ITEM DESCRIPTION	QUANTITY	UNITS
1	GENERAL CONDITIONS AND MOBILIZATION	1	LS
2	CONSTRUCTION SURVEY	1	LS
3	TOPOSOIL STRIP, STOCKPILE AND RESPREAD	1,330	CY
4	EXCAVATION AND BACKFILL, SEPTIC TANKS	962	CY
5	2" WATER SUPPLY, DIRECTIONAL BORE	297	LF
6	2" WATER SUPPLY, TRENCHED	32	LF
7	4" WATER TAP, CURB STOP	1	EA
8	1.5" SANITARY FORCEMAIN, DIRECTIONAL BORE	880	LF
9	6" SCHEDULE 40 PVC, SANITARY PIPING, TRENCHED	47	LF
10	4" SCHEDULE 40 PVC, SANITARY PIPING, TRENCHED	295	LF
11	MANHOLE, SEPTIC DISTRIBUTION BOX	1	EA
12	SEPTIC TANKS, 2,500 GALLON	6	EA
13	COCONUT FILTER TANKS AND DISTRIBUTION BOX	6	EA
14	PUMP TANKS, 1,500 GALLON	1	EA
15	SOIL BED MATERIAL EXCAVATION AND PLACEMENT	1,680	CY
16	DISTRIBUTION PIPING, SOIL BEDS, 2" SCHEDULE 40 PVC PRESSURE PIPE	764	LF
17	1.5" - 2.5" WASHED GRAVEL, SOIL BED	562	TON
18	PERFORATED DISTRIBUTION PIPING, SOIL BEDS, 2" SCHEDULE 40 PVC	1,380	LF
19	4" PERFORATED TILE	693	LF
20	TILE CLEANOUT	2	EA
21	PUMPS AND CONTROLS, SIMPLEX	2	EA
22	ELECTRICAL SERVICE AND CONNECTIONS	2	LS
23	DUMP STATION, INLET AND CONCRETE	2	EA
24	DUMP STATION, HYDRANTS	2	EA
25	SWPPP, MANAGEMENT	1	LS
26	SEEDBED PREPARATION	2.3	AC

	LEGEND		
Ε>	KISTING GENERAL SITE		
PLAN MARK	DESCRIPTION		
	EXISTING STRUCTURE		
•	BOLLARD		
	SHRUB		
\bigcirc	DECIDUOUS TREE		
Maria Cara Cara Cara Cara Cara Cara Cara	CONIFEROUS TREE		
-	SINGLE POLE SIGN		
- o- o-	DOUBLE POLE SIGN		
	TREE LINE		
— — —621— — —	MINOR CONTOUR		
— — —620 — — —	MAJOR CONTOUR		

	LITUITIEO	╡
PLAN MARK	UTILITIES DESCRIPTION	1
\bowtie^{W}	WATER IRRIGATION VALVE	1
ØØ	UTILITY POLE W/TRANSFORMER	1
0<	SIREN POLE	
\otimes	WATER SHUTOFF VALVE	1
—)	GUY ANCHOR	1
þ	FIRE HYDRANT	
	FLARED END SECTION	
\bowtie	VAL V E	
\otimes	STOP BOX	
C	CABLE TV PEDESTAL	
0	CLEANOUT	
J	JUNCTION BOX	
MH	MANHOLE	
(D)	STORM MANHOLE	
(E)	ELECTRICAL MANHOLE	
S	SANITARY MANHOLE	
①	TELEPHONE MANHOLE	
T	TELEPHONE PEDESTAL	
V	VAULT BOX	
НН	HANDHOLE	
S	SIGNAL BOX	
G	GAS METER	
E	ELECTRIC METER	
W	WATER METER	
	CURB INLET	
\ominus	INTAKE - CIRCLE	
	INTAKE - RECTANGLE	
	INTAKE - SQUARE	

UMP

LEGEND

	LEGEND	
	UTILITY LINES	
EXISTING LINE TYPE	DESCRIPTION	PROPOSED LINE TYPE
OE	ELECTRIC - OVERHEAD	OE
— — — E— — —	ELECTRIC - UNDERGROUND	— — — E— — —
-G	GAS MAIN	
W	WATER MAIN	w
))	SANITARY SEWER	
· · · · · · · · · · · · · · · · · · ·	STORM SEWER	
T	TELEPHONE - UNDERGROUND	
— — —FO— — —	FIBER OPTICS	FO—
	HIGH VOLTAGE ELECTRICAL	
<u>-</u>	LOW VOLTAGE ELECTRICAL	L


NOTES ISSU DATI

sts\DM\4217760\Deliverables\Drawings\1_Civil\C

С


C00





SOIL BED AREA SWPPP

DUMP STATION AREA SWPPP



STORMWATER POLLUTION PREVENTION NOTES

- ALL REQUIRED RECORD KEEPING. ALL RECORDS SHALL BE SUBMITTED TO THE OWNERS REPRESENTATIVE AS THEY ARE PRODUCED.
- 2. THE SEDIMENT CONTROLS IDENTIFIED ON THIS DRAWING MUST BE INSTALLED PRIOR TO ITEMS INCLUDE, BUT ARE NOT LIMITED TO, PERIMETER CONTROLS, STABILIZED CONSTRUCTION ENTRANCES, INTAKE PROTECTION, AREAS OF CONCENTRATED FLOW AND STOCKPILE PROTECTION.
- EROSION / SEDIMENTATION CONTROL MEASURES SHOULD BE INSTALLED BEFORE EARTH DISTURBING ACTIVITIES BEGIN AND ARE REQUIRED REGARDLESS OF THE TIME OF YEAR. THIS PLAN AND ITS ASSOCIATED REQUIREMENTS FOR THE PERMIT MUST BE IMPLEMENTED DURING WINTER MONTHS AS WELL.
- 4. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTROL EROSION/SEDIMENTATION ON THE SITE AT ALL TIMES. THE CONTROL MEASURES SHOWN ON THE PLAN ARE A MINIMUM. THE CONTRACTOR SHALL PROVIDE ADDITIONAL EROSION/SEDIMENTATION CONTROL MEASURES AS NECESSARY TO FULFILL THIS REQUIREMENT. CONTRACTOR IS REQUIRED TO MAINTAIN SWPPP DOCUMENTATION.
- 5. THE CONTRACTOR IS REQUIRED TO USE STABILIZATION CONTROLS FOR AREAS THAT WILL NOT BE REDISTURBED FOR 14 DAYS OR MORE. STABILIZATION MEASURES WILL BE IMPLEMENTED IMMEDIATELY AFTER CONSTRUCTION ACTIVITY HAS CEASED IN THAT AREA. STABILIZATION MEASURES ARE REQUIRED TO PREVENT BOTH SEDIMENTATION AND EROSION. THE CONTRACTOR IS STRONGLY ENCOURAGED TO PROVIDE STABILIZATION CONTROLS FOR ALL DISTURBED AREAS ON SITE REGARDLESS OF THE TIME PERIOD BEFORE THEY WILL BE DISTURBED AGAIN. THE CONTRACTOR SHALL SEED DISTURBED AREAS AS SOON AS WORK IS COMPLETED AS INDICATED ON THE PLANS AND PROJECT MANUAL
- 6. THE CONTRACTOR SHALL USE CONTROL MEASURES AS REQUIRED TO KEEP SOILS FROM LEAVING THE SITE.
- 7. CONTRACTOR SHALL IMPLEMENT SITE SPECIFIC BEST MANAGEMENT PRACTICES (BMPS) AS SHOWN AND REQUIRED BY THE SWPPP/SESC. ADDITIONAL BEST MANAGEMENT PRACTICES SHALL BE IMPLEMENTED BY THE CONTRACTOR AS DICTATED BY SITE CONDITIONS OR THE PROJECT GOVERNING AUTHORITIES AT NO ADDITIONAL COST TO THE OWNER THROUGHOUT ALL PHASES OF CONSTRUCTION.

- THE CONTRACTOR IS THE CO-APPLICANT FOR THE NPDES PERMIT AND IS REQUIRED TO DO 8. IF AFTER REPEATED FAILURE ON THE PART OF THE CONTRACTOR TO PROPERLY CONTROL SOIL EROSION, SEDIMENT AND/OR POLLUTION FROM THE PROJECT SITE, THE GOVERNING AUTHORITIES RESERVE THE RIGHT TO EFFECT NECESSARY CORRECTIVE MEASURES AND CHARGE ANY COSTS TO THE CONTRACTOR.
- SOIL-DISTURBING ACTIVITIES AND ARE TO REMAIN THROUGHOUT CONSTRUCTION. THESE 9. ALL BMPS AND CONTROLS INSTALLED ON GREEN INFRASTRUCTURE SHALL REMAIN UNTIL STABILIZATION IS APPROVED BY THE OWNER.
 - 10. IN THE EVENT THAT SOILS LEAVE THE SITE, CLEANUP OF ALL SURROUNDING ROADS, DRIVES, AND PARKING LOTS SHALL BE PERFORMED ON A DAILY BASIS AT A MINIMUM AND UPON REQUEST BY OWNER'S REPRESENTATIVE AT NO ADDITIONAL COST. PAVEMENT IS TO BE SCRAPED OF DEBRIS AND MUD AND BROOMED CLEAN. MUD TRACKS ARE TO BE REMOVED AS THEY ARE CREATED.
 - 11. IF AFTER REPEATED FAILURE ON THE PART OF THE CONTRACTOR TO PROPERLY CONTROL SOIL EROSION, SEDIMENT AND/OR POLLUTION FROM THE PROJECT SITE, THE GOVERNING AUTHORITIES RESERVE THE RIGHT TO EFFECT NECESSARY CORRECTIVE MEASURES AND CHARGE ANY COSTS TO THE CONTRACTOR.
 - 12. IF DURING CONSTRUCTION OPERATIONS ANY LOOSE MATERIALS ARE DEPOSITED IN THE FLOW LINE OF GUTTERS, DRAINAGE STRUCTURES, OR DITCHES SUCH THAT THE NATURAL FLOW LINE OF WATER IS OBSTRUCTED, THIS LOOSE MATERIAL SHALL BE REMOVED.
 - 13. ALL SEDIMENT SHALL BE PREVENTED FROM ENTERING ANY EXISTING STORM DRAINAGE SYSTEMS BY THE USE OF INLET PROTECTION OR OTHER APPROVED FUNCTIONAL METHODS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING SEDIMENT RESULTING FROM CONSTRUCTION ACTIVITIES ASSOCIATED WITH THIS PROJECT.
 - 14. CONSTRUCTION ACCESS POINTS TO THE SITE SHALL BE PROTECTED IN SUCH A WAY AS TO PREVENT TRACKING OF MUD OR SOIL ONTO PUBLIC THOROUGHFARES. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY MUST BE REMOVED IMMEDIATELY BY THE CONTRACTOR.
 - 15. MAINTAIN SILT FENCING AT ALL TIMES IN AN UPRIGHT POSITION. CLEAN SILT FROM FENCING ON A REGULAR BASIS AS PER THE STANDARD SPECIFICATIONS.SILT FENCES MUST BE CLEANED OUT WHEN THEY ARE 50% FULL.
 - 16. CONTRACTOR TO LOCATE/ RELOCATE SILT FENCING/ FILTER SOCKS AS NECESSARY

- THROUGHOUT THE PROJECT TO CONTROL EROSION/SEDIMENTATION. SILT FENCE INSTALLATION IS TO FOLLOW SUDAS 9040.119. FILTER SOCK INSTALLATION IS TO FOLLOW SUDAS 9040.102.
- 17. REMOVE ALL TEMPORARY EROSION/SEDIMENTATION CONTROLS NOT CALLED OUT TO REMAIN AFTER SITE HAS BEEN STABILIZED AND APPROVED BY THE OWNER'S REPRESENTATIVE. OWNER WILL REMOVE SILT FENCE AFTER SITE HAS STABILIZED.
- 18. CONTRACTOR TO USE EXTREME CAUTION WHILE INSTALLING SILT FENCE OR OTHER EROSION CONTROL DEVICES SO AS NOT TO DAMAGE UNDERGROUND UTILITIES.
- 19. EROSION CONTROL BLANKETS SHALL BE USED IN AREAS OF 4:1 SLOPE OR STEEPER AND ANY AREAS STABILIZED IN THE FALL FOR OVERWINTERING. OWNER WILL FURNISH AND INSTALL ALL EROSION CONTROL BLANKET AND SEEDING AFTER THE SITE IS FINAL GRADED AND SEEDED.OWNER WILL SEED ALL COVER CROPS AND PERMANENT VEGETATION.
- 20. SANITARY WASTE DISPOSAL: PORTABLE REST ROOM FACILITIES ARE ANTICIPATED TO BE PLACED ON-SITE. IN THE EVENT THAT PORTABLE REST ROOM FACILITIES ARE USED ON-SITE, THE CONTRACTOR IS REQUIRED TO INSTALL AN EROSION CONTROL DEVICE AROUND THE FACILITY TO MINIMIZE THE RADIUS OF THE AFFECTED ZONE IN THE EVENT OF 26. STOCKPILED MATERIALS: CONTRACTOR TO IDENTIFY ALL LOCATIONS OF STOCKPILED A SPILL. WASTES SHALL BE COLLECTED AND DISPOSED OF IN COMPLETE COMPLIANCE WITH LOCAL, STATE AND FEDERAL REGULATIONS. PORTABLE RESTROOM FACILITIES MUST NOT BE LOCATED NEAR DRAINAGE WAYS AND SHALL BE STAKED INTO THE GROUND.
- 21. IDENTIFICATION OF ALLOWABLE NON-STORMWATER DISCHARGES: DURING CONSTRUCTION, WHICH INCLUDES WATER FLUSHED FROM WATER LINES, PAVEMENT AND EQUIPMENT WASHING, AND GROUNDWATER (DEWATERING), SHOULD BE FILTERED WITH APPROPRIATE METHODS AND DIRECTED AWAY FROM DRAINAGE WAY.
- 22. POLLUTION AND SPILL PREVENTION PLANNING: POTENTIALLY HAZARDOUS MATERIALS ON THE CONSTRUCTION SITE INCLUDE FUEL, LUBRICANTS, CURING COMPOUNDS, FERTILIZERS, GREASE AND CLEANING SOLVENTS. ALL REASONABLE PRECAUTIONS WILL BE TAKEN TO PREVENT SPILLS. ANY SPILLED MATERIAL WILL IMMEDIATELY BE DIRECTED AWAY FROM STORM WATER INTAKES, DETENTION BASINS, OR DRAINAGE WAYS. SPILLED MATERIALS WILL BE CLEANED AND, IF NECESSARY, SOIL REMEDIATION PRACTICES WILL BE USED, A RECORD OF SPILLS WILL BE MAINTAINED BY THE MAIN CONTRACTOR.

- 23. CONCRETE, PAINT AND GROUT WASHOUT AREA: THE WASHOUT AREA SHOULD BE AN APPROVED CONCRETE WASHOUT CONTAINER, COLLECTION BAG, OR WASHOUT BOX PER SUDAS 11.050. PROTECT WITH AN EROSION CONTROL DEVICE (IF USING FILTER SOCKS. STACK TWO (2) TALL). CONTRACTOR TO HAUL OFF ALL WASTE MATERIAL. ALL LOCATIONS OF CONCRETE. PAINT AND GROUT WASHOUT AREAS MUST BE PROVIDED BY THE CONTRACTOR AND IDENTIFIED ON THE PLAN (RELOCATE AS REQUIRED FOR CONSTRUCTION). THE CONTRACTOR IS REQUIRED TO INSTALL A SIGN THAT DESIGNATES THE WASHOUT AREA.
- 24. SPILL KIT: A SPILL KIT IS REQUIRED TO BE ON-SITE AND LOCATION NOTED ON THE STORMWATER POLLUTION PREVENTION PLAN. THE SPILL KIT SHOULD BE DESIGNED TO DEAL WITH ANY HAZARDOUS MATERIALS ON-SITE.
- 25. DUST CONTROL: THE CONTRACTOR SHALL IMPLEMENT DUST CONTROL MEASURES WHERE DUST IS GENERATED. FREQUENT WATERING OF THE SITE, SPRINKLED, VEGETATIVE COVER, MULCH, WINDBREAKS, TILLAGE, STONE AND SPRAY-ON CHEMICAL SOIL TREATMENTS (PALLIATIVES) ARE POSSIBLE DUST CONTROL MEASURES. IF THE DUST CONTROL IS NOT ACCEPTABLE IT SHALL BE CHANGED AS DIRECTED BY THE OWNER'S REPRESENTATIVE.
- MATERIALS ON THE STORMWATER POLLUTION PREVENTION PLAN. CONTRACTOR SHALL PROVIDE ALL EROSION/SEDIMENTATION CONTROLS AS REQUIRED TO CONTAIN MATERIALS ON-SITE. AT A MINIMUM, THE CONTRACTOR IS REQUIRED TO PROVIDE SILT FENCE/FILTER SOCKS AROUND STOCKPILED SOILS BEFORE STOCKPILE IS RE-SPREAD. IF STOCKPILE SOILS WILL REMAIN INACTIVE FOR 14 DAYS OR MORE, THEY SHALL BE SEEDED OR TARPED BY THE CONTRACTOR
- 27. THE CONTRACTOR SHALL AMEND THE SWPPP WHENEVER THERE IS A CHANGE IN DESIGN, CONSTRUCTION, OPERATION OR MAINTENANCE OF A STORMWATER BMP.

