Office Use Only



\$ \$ Fee





JOHNSON COUNTY, IOWA

APPLICATION FOR: CONDITIONAL USE PERMIT



	The state of the s
	state the official use as listed in the Johnson County UDO, and lustry for Antique shop, Special Events for Corn Maze, etc.]):
On property located at (street address if available 260th St NW, at the end of Ireland Ave N	ole or layman's description): W, near North Liberty (Parcel Number: 0609351001).
Parcel Number(s): 0609351001	
7.50	s, and is currently zoned 4
Development Ordinance and any other condition	to any conditions outlined in chapter 8:1.23 of the Unified ns deemed appropriate by the board of Adjustment to protect of the safety, and welfare.
affirms that the owner(s) of the property described of	ed herein is true and correct. If applicant is not the owner, applicant on this application consent to this application being submitted, and e of Johnson County Planning, Development, and Sustainability to erty.
Double Dime Acres	Peterson Contractors, Inc.
Name of Owner	Name of Applicant (if different)
104 Blackhawk Street Reinbeck, IA 50669	
Applicant Street Address (including City, State, Zip	p)
Applicant Phone Applican	nt Email
Tyler Gustafson, PE Chi. Lipida Jajanet by Tyler Gustafson, PE Chi. Tyl	

See back page for Application Submittal Requirements and Checklist

Applications should be emailed to planning@johnsoncountyiowa.gov and delivered to the Planning,

Development and Sustainability Office (913 South Dubuque Street, Iowa City, IA 52240)

Applicant Signature

JUN 1 1 2025

The following items must be submitted for the application to be complete. Incomplete applications will be retain will not be considered until the next submission deadline. Once submitted, county staff will review the materials and request revisions (if necessary). Once all revisions and outside reviews have been received, the application will be placed on the next available Board of Adjustment agenda.

If working with an engineer who can provide CAD or GIS line work, electronic submissions should be submitted in accordance with the PDS department's electronic submission guidelines (see below). Preference is that electronic submission is prior to hard copy submission, but will be accepted until 12:00 p.m. the day after the submittal deadline.

Initial each empty box below to ensure you included all necessary information in the appropriate form for an application to be considered complete. Some items may require both electronic and physical copies.

Item Required	Electronic Copy (PDF unless otherwise noted)	Hard copy
Application Fee (varies based on application. Fee: \$_250_)		
This application form with all information completed	TG	(2)
Brief cover letter explaining the proposed use including but not limited to the number of employees, parking facilities, days and hours of operation, estimate of maximum number of customers expected on site an any one time, provisions for water and wastewater, types of equipment to be used, signage, etc	TG O	
Site plan identifying the access, structure(s) for the proposed use, parking areas, signage location, and addressing any Supplemental Conditions required by Chapter 8:1.23	TG	
If working with an engineer: CAD line work of the site plan, following the guidance below	TG	
Proof of application to the Johnson County Health Department for a Public Health Zoning Application	TG _	
 For requests to establish Utility Scale Solar (use area of 20 acres or less): Completed "Application Checklist for Utility-Scale Solar Systems (Supplemental Conditions)", accompanied by all information outlined on said checklist. Electronic Submission of all materials is required. 		
 For requests for Commercial Communications Towers, include the following: Sensitive Areas Analysis in compliance with the Sensitive Areas Ordinance, or an approved Sensitive Areas waiver. Stormwater Management Plan (including soil erosion and sediment control) in compliance with the Stormwater Management regulations, or an approved waiver 		

Electronic Submission Requirements for CAD line work:

- Must be in AutoCAD 2017 or older and .dwg format (.dxf is also acceptable, no .zip files will be accepted).
- Submissions must use Coordinate System: NAD_1983_StatePlane_lowa_South_FIPS_1402_Feet
- If applicable, submission should include information for Sensitive Areas Analysis/Mapping and Stormwater/Soil Erosion Control infrastructure on the site. This includes any limits of disturbance or other impact areas.
- Submission should NOT include legends, legal descriptions, location maps, signature blocks, etc.



LETTER OF TRANSMITTAL

TIETERSTM

PO Box A

104 Blackhawk

NUTBOLT	TIDE R	einbeck, IA 506	69	Date:	2/25/2025	PCI No:	J24474
	I UILZ	Ph) (319) 345	5-2713	Atte	ention:	Troy	Mertens
NE.	I O W A	F) (319) 345		RE:	Co F	Rd F28/Penn S	t over I-380
H D C C R					North Li	berty, IA - Joh	nson Co.
Streb C		on Company	Inc.				9)(403)(404)(456)(469
	PO Bo			Con	tract No	52-3	806-393
(Coralville,	IA 52241					
tlemen:	<u> </u>				7		
	2000	- 1 to 1 t	Und	ler Separa	te cover via	the fo	llowing items
Drawing	· ·	Prints		ns	Samples	Specificatio	ns
Copy of	letter _	Change O	der 🔲 _				
Copies	Date	Number			Desc	cription	
Copies	Date	Iddilipei			Desc	лрион	
	1 = 10 01	00.00050	OA ENEDAN	LUMPAIT	IN DI ACE	CONTRACTO	OD ELIDNISHED
Item	1510 21	02-26250	UT EMBAN	MINENI	-IN-PLACE,	CONTRACTO	OR FURNISHED
1	2/25/25	1	Iowa DOT	Proposa	aed Borrow Id	lentification F	orm (1 Page)
1	2/25/25	1	Borrow Loc	cation Ma	p (2 Pages)		
1	2/25/25	1	Borrow De	esign Qu	antity Analys	is (1 Page)	
1	2/25/25				gs (3 Pages)		
1	2/25/25	1				tics (23 Page	s)
1		4			tions (3 Page		
1	2/25/25		BOITOW CI	033 000	tiono (o r ago	<u> </u>	
	-						
VEGERAND	rovol		RE	MARKS:	Urgency of r	eview: Expe c	lited
X For app							
For you							
As requ		nonaurona	-				
	ed as sub		-				
	ed as not		-				
Returne	ed for con	rections	<u> </u>				
Resubn	nit	copies for a	pproval				
Submit	cc	pies for dist	ribution				
Return		correcte	d prints				
	iew and c			c:			
For hide	s due	1	Account to the second s				
		ifter loan to i				mm.	Manimum COUNTY



IOWA DOT PROPOSED BORROW IDENTIFICATION FORM

Date 1/9/2025	4		
Project Numbe	r <u>IM-NHS-380-6(456)1</u>	3-52	County Johnson
Project Descrip	HMA Pavement - otion Penn St / Co Rd		
Contractor Per	terson Contractors Inc.		Phone
1. Borrow	ID Number: J24474		
2. Locatio	n (Legal Description):	Section 9, Towns	ship 80, Range 7 in Johnson County, IA
3. Size (ad	cres): 7.50 Acres		
4. Type: الا	Drainable Borrow Pond Borrow Other		Stockpiled Borrow – Closed/Existing Stockpiled Borrow – Open/Active
5. Estimat	ted excavation quantit		s):
	Class 10 (suitable)	Name of the same o	
	Select		
	Unsuitable	0	
6. Contrac	ctor contact if addition		required:
	Name Tyler Gusta	awk St Reinbeck, IA	
	Address	awk of Relibeck, IA	
	Phone Email	No. 200	
	E 1117111		





Job: Double Dime Acres Borrow Units: Ft-CY Thu Jan 9, 2025 14:31:31 Page 1

Volume Report Design vs. Existing

		Area			Volum	ne	Comp/	Ratio	Comp			Change
Name	Total	Cut	FIII	OnGrade	Cut	FIII	Cut	FIII	Cut		The second second	Per 0.1 ft
Job Site	326,370	326,135	45	190	103,950	0	1.00	1.00	103,950	0	103,950	1,209

Iowa DOT BO 103 Johnson County - Penn Street and I-380 - Borrow (PCI J24474) North Intersection of N Ireland Ave and 260th Street NW | North Liberty, IA Terracon Project No. 06251002



Boring Log No. B-1

						Atterbero
	£	vel	ype	щЖ	(%)	Atterberg Limits
	h (F	r Le	ple T	MPL	/ate	
	Sept	Nate Obse	Sam	SN	Cont	LL-PL-PI
oproximate Elevation: 806 (Ft.)		-0				
	- 50					
	-					
	-					
				0002	7.9	NP
	_			,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		25550
	5-					
	-					
	_					
798	_				101777	
	10-					
	-			0010	24.4	NP
	-			.0010	24.4	ive
	_					
701						
791	15					
						÷
						ĺ
		11	1			
						ļ
		8				
Water Level Observations					Drill	Rig
Water Level Observations ☐ 10' while drilling and same	pling				Drill 603 -	Rig CME 850XI
	pling					
	pling				Drille 603 -	Rig CME 850XF
	798	798 798 798	798 10 V	798 10————————————————————————————————————	798 10 .0002 .0010	798 10

Abandonment Method Boring backfilled with auger cuttings upon completion. Boring Started 01-28-2025

Boring Completed 01-28-2025 Iowa DOT BO 103 Johnson County - Penn Street
and I-380 - Borrow (PCI J24474)
North Intersection of N Ireland Ave and 260th Street NW | North Liberty, IA
Terracon Project No. 06251002



Boring Log No. B-2

Location: See Exploration Plan		÷	le l	be		(%)	Atterberg Limits	
Latitude: 41.7461° Longitude: -91.6754°		Depth (Ft.)	Water Level Observations	Sample Type	SAMPLE	Water Content (%)	LL-PL-PI	
	Approximate Elevation: 818 (Ft.) 5/4)							
		-						
		5-			.0005	5.6	NP	
		-						
8.0 POORLY GRADED SAND (SP), brown (7.5YR 5/6)	810	=	-					
		10-						
		-						
		-	∇					
		-			.0004	7.7	NP	
		15-	1					
18.0	800	-						
SILTY CLAYEY SAND (SC-SM), gray brown (7.5YR 4/1)		-						
		20-					35.000	
		-			.0003	26.2	17-13-	
25.0 Boring Terminated at 25 Feet	793	25	-					
se Exploration and Testing Procedures for a description of field and laboratory ocedures used and additional data (If any). se Supporting Information for explanation of symbols and abbreviations.	Water Level Observations 13' while drilling and same	pling				Drill I 603 -	Rig CME 850XF	
otes	Advancement Method					Driller SZ		
	Flight Auger	Logged by						
	Abandonment Method Boring backfilled with auger co	uttings u	ipon c	omple	etion.		g Started 3-2025 g Complet	

Boring Completed 01-28-2025 Iowa DOT 80 103 Johnson County - Penn Street and I-380 - Borrow (PCI J24474) North Intersection of N Ireland Ave and 260th Street NW | North Liberty, 1A Terracon Project No. 06251002



Boring Log No. B-3

Location: See Exploration Plan	7	le su	be		(%)	Atterberg Limits
Latitude: 41.7461° Longitude: -91.6745°	Depth (Ft.)	Water Level Observations	Sample Type	SAMPLE	Water Content (%)	LL-PL-PI
Depth (Ft.) Approximate Elevation: 817 (Ft.) POORLY GRADED SAND WITH SILT (SP-SM), brown (7.5YR 2.5/2)			. =			
	5-			.0009	6.0	NP
8.0 POORLY GRADED SAND WITH SILT (SP-SM), brown (7.5YR 5/4)	-					
13.0	10-	∇		.0008	5.3	NP
13.0 80 POORLY GRADED SAND (SP), brown (7.5YR 5/6)	1 -					
	15-			.0007	17.4	NP
18.0 79 SANDY LEAN CLAY (CL), trace gravel, brown (7.5YR 3/1)	9	-				
SANDY LEAN CLAY (CL), trace graver, brown (7.31K 3/1)	20-			2000		
				.0006	21.0	24-13-1
23.0 79 Boring Terminated at 23 Feet	4					
Exploration and Testing Procedures for a description of field and laboratory Exploration and Testing Procedures for a description of field and laboratory Water Level Observations 2 12' while drilling and same					Drill	Rig CME 850XR

See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (If any).

See Supporting Information for explanation of symbols and abbreviations.

Advancement Method
Flight Auger

Abandonment Method
Boring backfilled with auger cuttings upon completion.

Drill Rig
503 - CME 850XR

Driller
52
Logged by
33E

Boring Started
01-28-2025

Boring Completed
01-28-2025

Report Number: 06251002.0002

Service Date:

01/29/25

Report Date:

02/20/25 Revision 1 - Update with Hydrometer

Task:

Laboratory Testing Services

2640 12th St SW

Cedar Rapids, IA 52404-3440

319-366-8321

Client

Peterson Contractors, Inc.

Attn: Matt Bohlen

104 Blackhawk St PO Box A

Reinbeck, IA 50669-1012

Material Information

Source of Material:

Proposed Use:

Project

Iowa DOT BO 103 Johnson County- Penn Street and I-380 - Borrow (PCI.

North Intersection of N Ireland Avenue and 260th Street NW

DOT #IM-NHS-380-6(393)3--03-52

North Liberty, IA

Project Number: 06251002

Sample Information

Borrow site Sample Date:

01/29/25

Sampled By:

Liquid Limit:

Everman, Jeremy

Sample Location:

B-1, EL = 0'-8'

Sample Description: Brown (7.5 yr 4/6) Fine to Medium Sand

Laboratory Test Data

Test Procedure:

ASTM D698

Grading

Test Method:

Sample Preparation: Wet Manual

Rammer Type:

Maximum Dry Unit Weight (pcf):

Optimum Water Content (%):

Method A

11.4

111.9

Result

Specifications

Non-plastic

Plastic Limit: Plasticity Index:


Non-plastic Non-plastic

In-Place Moisture (%):

24.4

USCS:

Zero Air Voids Curve for Assumed Specific Gravity



Water Content (%)

Comments: Report will be updated once hydrometers are completed

Services:

Obtain a sample of fill material at a borrow site and return it to the laboratory. Prepare and test the sample for standard Proctor

moisture-density relationship.

Terracon Rep.: Dillon Nolan

Reported To:

PCI Contractor:

Report Distribution:

(1) Peterson Contractors, Inc., Matt Bohlen

(1) Peterson Contractors, Inc., Tyler Gustafson

(1) Peterson Contractors, Inc., Zach Steffen

(1) Terracon Consultants, Inc., Peng Cavan

Reviewed By:

Project Engineer

Test Methods:

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.

Page 1 of 1

Report Number: 06251002.0010

Service Date:

01/29/25

Report Date:

PO Box A

Revision 1 - Update with Hydrometer 02/20/25

Task:

Client

Laboratory Testing Services

Project

Iowa DOT BO 103 Johnson County- Penn Street and I-380 - Borrow (PCI.

319-366-8321

2640 12th St SW

Cedar Rapids, IA 52404-3440

North Intersection of N Ireland Avenue and 260th Street NW

DOT #IM-NHS-380-6(393)3--03-52

North Liberty, IA

Project Number: 06251002

Reinbeck, IA 50669-1012 **Material Information**

Peterson Contractors, Inc.

Source of Material:

Borrow site

Proposed Use:

Attn: Matt Bohlen

104 Blackhawk St

Grading

Sample Information

Sample Date:

01/29/25

Sampled By:

Liquid Limit:

Plastic Limit:

Plasticity Index:

In-Place Moisture (%):

Everman, Jeremy

Sample Location:

B-1, EL = 8'-15'

Result

Non-plastic

Non-plastic

Non-plastic

24.4

Sample Description: Brown (7.5 yr 4/3) Fine to Medium Sand

Laboratory Test Data

Test Procedure:

ASTM D698

Test Method:

Method A

Sample Preparation: Wet

Manual

Rammer Type:

Maximum Dry Unit Weight (pcf):


109.2 12.7

Optimum Water Content (%):

USCS:

Zero Air Voids Curve for Assumed Specific Gravity

Specifications



Water Content (%)

Comments: Report will be updated once hydrometers are completed

Services:

Obtain a sample of fill material at a borrow site and return it to the laboratory. Prepare and test the sample for standard Proctor moisture-density relationship.

Terracon Rep.: Dillon Nolan

Reported To:

PCI Contractor:

Report Distribution:

- (1) Peterson Contractors, Inc., Matt Bohlen
- (1) Peterson Contractors, Inc., Tyler Gustafson
- (1) Peterson Contractors, Inc., Zach Steffen
- (1) Terracon Consultants, Inc., Peng Cavan

Reviewed By:

Project Engineer

Test Methods:

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.

Page 1 of 1

Report Number: 06251002.0003

Service Date:

01/29/25

Report Date:

02/21/25

Revision 1 - Update with Hydrometer

Task:

Laboratory Testing Services

2640 12th St SW

Cedar Rapids, IA 52404-3440

319-366-8321

Client

Peterson Contractors, Inc.

Attn: Matt Bohlen 104 Blackhawk St

PO Box A

Reinbeck, IA 50669-1012 **Material Information**

Source of Material:

Proposed Use:

Project

Iowa DOT BO 103 Johnson County- Penn Street and I-380 - Borrow (PCI .

North Intersection of N Ireland Avenue and 260th Street NW

DOT #IM-NHS-380-6(393)3--03-52

North Liberty, IA

Project Number: 06251002

Sample Information

Sample Date:

01/29/25

Sampled By:

Everman, Jeremy

Sample Location:

B-2, EL = 20'-25'

Sample Description: Gray Brown (7.5 yr 4/1) Silty Clayey Sand

Laboratory Test Data

Test Procedure: Test Method:

ASTM D698

118.5

11.6

Borrow site

Grading

Method A

Sample Preparation: Wet

Rammer Type: Mechanical

Maximum Dry Unit Weight (pcf):

Optimum Water Content (%):

Liquid Limit:

Plastic Limit:

Plasticity Index:


In-Place Moisture (%):

Specifications Result 17 13

4 26.2

USCS:

Zero Air Voids Curve for Assumed Specific Gravity



Water Content (%)

Comments: Report will be updated once hydrometers are completed

Services:

Obtain a sample of fill material at a borrow site and return it to the laboratory. Prepare and test the sample for standard Proctor moisture-density relationship.

Terracon Rep.: Dillon Nolan

Reported To:

PCI Contractor:

Report Distribution:

- (1) Peterson Contractors, Inc., Matt Bohlen
- (1) Peterson Contractors, Inc., Tyler Gustafson
- (1) Peterson Contractors, Inc., Zach Steffen
- (1) Terracon Consultants, Inc., Peng Cavan

Reviewed By:

Project Engineer

Test Methods:

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.

Page 1 of 1

Report Number: 06251002.0004

Service Date:

01/29/25

Report Date:

Revision 1 - Update with Hydrometer 02/21/25

Task:

Laboratory Testing Services

2640 12th St SW

Cedar Rapids, IA 52404-3440

319-366-8321

Client

Peterson Contractors, Inc.

Attn: Matt Bohlen 104 Blackhawk St

PO Box A

Reinbeck, IA 50669-1012 **Material Information**

Source of Material:

Proposed Use:

Project

Iowa DOT BO 103 Johnson County- Penn Street and I-380 - Borrow (PCI.

North Intersection of N Ireland Avenue and 260th Street NW

DOT #IM-NHS-380-6(393)3--03-52

North Liberty, IA

Project Number: 06251002

Sample Information

Borrow site Sample Date:

01/29/25

Sampled By:

Liquid Limit:

Everman, Jeremy

Sample Location:

B-2, EL = 9'-18'

Sample Description: Brown (7.5 yr 5/6) Fine to Medium Sand

Laboratory Test Data

Test Procedure: Test Method:

Method A

Grading

Sample Preparation: Wet

Mechanical

Rammer Type:

Maximum Dry Unit Weight (pcf):

Optimum Water Content (%):

ASTM D698

117.7

7.0

Result

Specifications

Non-plastic

Plastic Limit:


Non-plastic Non-plastic

Plasticity Index: In-Place Moisture (%):

7.7

USCS:

Zero Air Voids Curve for Assumed Specific Gravity



Water Content (%)

Comments: Report will be updated once hydrometers are completed

Services:

Obtain a sample of fill material at a borrow site and return it to the laboratory. Prepare and test the sample for standard Proctor moisture-density relationship.

Terracon Rep.: Dillon Nolan

Reported To:

Contractor:

PCI

Report Distribution:

- (1) Peterson Contractors, Inc., Matt Bohlen
- (1) Peterson Contractors, Inc., Tyler Gustafson
- (1) Peterson Contractors, Inc., Zach Steffen
- (1) Terracon Consultants, Inc., Peng Cavan

Reviewed By:

Project Engineer

Test Methods:

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.

Page 1 of 1

Report Number: 06251002.0005

Service Date:

01/29/25

Report Date:

PO Box A

02/21/25 Revision 1 - Update with Hydrometer

Task: Client Laboratory Testing Services

Project

319-366-8321

2640 12th St SW

Cedar Rapids, IA 52404-3440

Iowa DOT BO 103 Johnson County- Penn Street and I-380 - Borrow (PCI.

North Intersection of N Ireland Avenue and 260th Street NW DOT #IM-NHS-380-6(393)3--03-52

North Liberty, IA

Project Number: 06251002

Reinbeck, IA 50669-1012

Peterson Contractors, Inc.

Attn: Matt Bohlen

104 Blackhawk St

Material Information

Source of Material:

Borrow site

Proposed Use:

Grading

Sample Information

Sample Date:

01/29/25

Sampled By:

Liquid Limit:

Plastic Limit:

Everman, Jeremy

Sample Location:

B-2, EL = 0'-8'

Sample Description:

Brown (7.5 yr 5/4) Fine to Medium Sand with

Specifications

Silt

Laboratory Test Data

Test Procedure:

ASTM D698

Test Method:

Method A

Sample Preparation: Wet

Rammer Type: Manual

Maximum Dry Unit Weight (pcf):

112.0 11.0

Optimum Water Content (%):

Result

Non-plastic

Non-plastic

Plasticity Index:


Non-plastic

In-Place Moisture (%):

5.6

USCS:

Zero Air Voids Curve for Assumed Specific Gravity



Water Content (%)

Comments: Report will be updated once hydrometers are completed

Services:

Obtain a sample of fill material at a borrow site and return it to the laboratory. Prepare and test the sample for standard Proctor moisture-density relationship.

Terracon Rep.: Dillon Nolan

Reported To:

PCI Contractor:

Report Distribution:

- (1) Peterson Contractors, Inc., Matt Bohlen
- (1) Peterson Contractors, Inc., Tyler Gustafson
- (1) Peterson Contractors, Inc., Zach Steffen
- (1) Terracon Consultants, Inc., Peng Cavan

Reviewed By:

Project Engineer

Test Methods:

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.

Page 1 of 1

Report Number: 06251002.0007

Service Date:

01/29/25

Report Date:

02/21/25

Revision 1 - Update with Hydrometer

Task:

Laboratory Testing Services

2640 12th St SW

Cedar Rapids, IA 52404-3440

319-366-8321

Client Peterson Contractors, Inc.

Attn: Matt Bohlen

104 Blackhawk St

PO Box A

Reinbeck, IA 50669-1012 Material Information

Source of Material:

Proposed Use:

Project

Iowa DOT BO 103 Johnson County- Penn Street and I-380 - Borrow (PCI.

North Intersection of N Ireland Avenue and 260th Street NW

DOT #IM-NHS-380-6(393)3--03-52

North Liberty, IA

Project Number: 06251002

Sample Information

Sample Date:

01/29/25

Sampled By:

Everman, Jeremy

Sample Location:

B-3, EL = 13'-18'

Sample Description: Brown (7.5 y 5/6) Fine to Medium Sand

Specifications

Laboratory Test Data

Test Procedure:

ASTM D698

Borrow site

Grading

Test Method:

Method A

Sample Preparation: Wet

Manual Rammer Type:

Maximum Dry Unit Weight (pcf):

Optimum Water Content (%):

109.1

13.1

Result

Non-plastic

Liquid Limit: **Plastic Limit:** Plasticity Index:


Non-plastic Non-plastic

In-Place Moisture (%):

17.4

USCS:

Zero Air Voids Curve for Assumed Specific Gravity



Water Content (%)

Comments: Report will be updated once hydrometers are completed

Services:

Obtain a sample of fill material at a borrow site and return it to the laboratory. Prepare and test the sample for standard Proctor moisture-density relationship.

Terracon Rep.: Dillon Nolan

Reported To:

Contractor: PCI

Report Distribution:

- (1) Peterson Contractors, Inc., Matt Bohlen
- (1) Peterson Contractors, Inc., Tyler Gustafson
- (1) Peterson Contractors, Inc. , Zach Steffen
- (1) Terracon Consultants, Inc., Peng Cavan

Reviewed By:

Project Engineer

Test Methods:

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.

Page 1 of 1

Report Number: 06251002.0008

Attn: Matt Bohlen

104 Blackhawk St

Service Date:

01/29/25

Report Date:

PO Box A

02/21/25 Revision 1 - Add Att

Task:

Client

Laboratory Testing Services

Project

Iowa DOT BO 103 Johnson County- Penn Street and I-380 - Borrow (PCI.

319-366-8321

2640 12th St SW

Cedar Rapids, IA 52404-3440

North Intersection of N Ireland Avenue and 260th Street NW

DOT #IM-NHS-380-6(393)3--03-52

North Liberty, IA

Project Number: 06251002

Reinbeck, IA 50669-1012 **Material Information**

Peterson Contractors, Inc.

Source of Material:

Borrow site

Proposed Use:

Grading

Sample Information

Sample Date:

01/29/25

Sampled By:

Everman, Jeremy

Sample Location:

B-3, EL = 8'-13'

Sample Description:

Brown (7.5 yr 5/4) Fine to Medium Sand with

Specifications

SIIt

Laboratory Test Data

Test Procedure: **Test Method:**

ASTM D698

Method A

Sample Preparation: Wet

Rammer Type:

Manual

Maximum Dry Unit Weight (pcf):

113.4 8.4

Optimum Water Content (%):

Result

Non-plastic

Liquid Limit: Plastic Limit:

Non-plastic

Plasticity Index:


Non-plastic

In-Place Moisture (%):

1.8

USCS:

Zero Air Voids Curve for Assumed Specific Gravity



Water Content (%)

Comments: Report will be updated once hydrometers are completed

Services:

Obtain a sample of fill material at a borrow site and return it to the laboratory. Prepare and test the sample for standard Proctor moisture-density relationship.

Terracon Rep.: Dillon Nolan

Reported To:

Contractor:

PCI

Report Distribution:

- (1) Peterson Contractors, Inc., Matt Bohlen
- (1) Peterson Contractors, Inc., Tyler Gustafson
- (1) Peterson Contractors, Inc., Zach Steffen
- (1) Terracon Consultants, Inc., Peng Cavan

Reviewed By:

Project Engineer

Test Methods:

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.

Page 1 of 1

Report Number: 06251002.0009

Service Date:

01/29/25

Report Date:

02/21/25 Revision 1 - Update with Hydrometer

Task:

Laboratory Testing Services

Cedar Rapids, IA 52404-3440

319-366-8321

2640 12th St SW

Client

Peterson Contractors, Inc.

Attn: Matt Bohlen 104 Blackhawk St

PO Box A

Reinbeck, IA 50669-1012 Material Information

Source of Material:

Proposed Use:

Project

Iowa DOT BO 103 Johnson County- Penn Street and I-380 - Borrow (PCI .

North Intersection of N Ireland Avenue and 260th Street NW

DOT #IM-NHS-380-6(393)3--03-52

North Liberty, IA

Project Number: 06251002

Sample Information

Sample Date:

01/29/25

Sampled By:

Everman, Jeremy

Sample Location:

B-3, EL = 0'-8'

Sample Description:

Brown (7.5 yr 2.5/2) Fine to Medium Sand with

Specifications

Silt

Laboratory Test Data

Test Procedure:

ASTM D698

112.2

10.6

Borrow site

Grading

Test Method:

Method A

Sample Preparation: Wet

Rammer Type: Mechanical

Maximum Dry Unit Weight (pcf):

Optimum Water Content (%):

Result Non-plastic

Liquid Limit:

Plastic Limit:

Plasticity Index:


In-Place Moisture (%):

Non-plastic 6.0

Non-plastic

USCS:

Zero Air Voids Curve for Assumed Specific Gravity 2.70



Water Content (%)

Comments:

Services:

Obtain a sample of fill material at a borrow site and return it to the laboratory. Prepare and test the sample for standard Proctor

moisture-density relationship.

Terracon Rep.: Dillon Nolan

Reported To:

PCI Contractor:

Report Distribution: (1) Peterson Contractors, Inc., Matt Bohlen

- (1) Peterson Contractors, Inc., Tyler Gustafson
- (1) Peterson Contractors, Inc., Zach Steffen
- (1) Terracon Consultants, Inc., Peng Cavan

Reviewed By:

Project Engineer

Test Methods:

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.

Page 1 of 1

Report Number: 06251002.0006

Service Date:

01/29/25

Report Date:

02/21/25

Revision 1 - Update with Hydrometer

Task:

Laboratory Testing Services

2640 12th St SW

Cedar Rapids, IA 52404-3440

319-366-8321

Client Peterson Contractors, Inc.

Attn: Matt Bohlen

104 Blackhawk St

PO Box A

Reinbeck, IA 50669-1012

Project

Iowa DOT BO 103 Johnson County- Penn Street and I-380 - Borrow (PCI .

North Intersection of N Ireland Avenue and 260th Street NW

DOT #IM-NHS-380-6(393)3--03-52

North Liberty, IA

Project Number: 06251002

Material Information

Source of Material:

Borrow site

Proposed Use:

Grading

Sample Information

Sample Date:

01/29/25

Sampled By:

Liquid Limit:

Plastic Limit:

Plasticity Index:

In-Place Moisture (%):

Everman, Jeremy

Sample Location:

B-3, EL = 19'-23'

Result

24

13

11

21.0

Sample Description:

Brown (7.5 yr 3/1) Sandy Lean Clay trace

Specifications

Gravel

Laboratory Test Data

Test Procedure:

ASTM D698

Test Method:

Method A

Sample Preparation: Wet

Rammer Type:


Manual Maximum Dry Unit Weight (pcf):

Optimum Water Content (%):

114.0 10.6

USCS:

Zero Air Voids Curve for Assumed Specific Gravity



Water Content (%)

Comments: Report will be updated once hydrometers are completed

Services:

Obtain a sample of fill material at a borrow site and return it to the laboratory. Prepare and test the sample for standard Proctor

moisture-density relationship.

Terracon Rep.: Dillon Nolan

Reported To:

PCI Contractor:

Report Distribution:

- (1) Peterson Contractors, Inc., Matt Bohlen
- (1) Peterson Contractors, Inc., Tyler Gustafson
- (1) Peterson Contractors, Inc., Zach Steffen
- (1) Terracon Consultants, Inc., Peng Cavan

Reviewed By:

Project Engineer


Test Methods:

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.


Page 1 of 1

2/20/25

North Liberty, IA



2640 12th St SW Cedar Rapids, IA




2640 12th St SW Cedar Rapids, IA

EXHIBIT: B-1

North Liberty, IA

2/20/25


BORROW (PCI J24474).GPJ TERRACON_DATATEMPLATE.GDT 2/20/25



North Liberty, IA



Reinbeck, IA



PROJECT: Iowa DOT BO 103 Johnson County - Penn Street and I-380


SITE: North Intersection Por Wireland Ave and 260th Street NW North Liberty, IA



PROJECT NUMBER: 06251002

CLIENT: Peterson Contractors, Inc. Reinbeck, IA

2/20/25




2640 12th St SW

Cedar Rapids, IA

260th Street NW

North Liberty, IA

CLIENT: Peterson Contractors, Inc. Reinbeck, IA



260th Street NW North Liberty, IA

2/20/25

TERRACON_DATATEMPLATE.GDT


GRAIN




CLIENT: Peterson Contractors, Inc. Reinbeck, IA

2/20/25

North Liberty, IA



2548 12th St SW Cedar Rapids, IA



SITE: North Intersection of Wireland Ave and

2/20/25

TERRACON_DATATEMPLATE.GDT


BORROW (PCI J24474).GPJ

260th Street NW North Liberty, IA



CLIENT: Peterson Contractors, Inc. Reinbeck, IA

2/20/25




2640 12th St SW Cedar Rapids, IA


260th Street NW


North Liberty, IA


CLIENT: Peterson Contractors, Inc. Reinbeck, IA

2/20/25










Borings B-1, B-2, and B-3


Terrecon Project No. 06251902

Boring	Depth to Top of Sample (ft)	Depth to Bottom of Sample (11)	Sample Type	(%) 77	PL (%)	PI (%)	Gravel (%) (> 2.0 mm)	Sand (%) (2.0 - 0.074 mm)	(0.074 - 0.002	Clay (%) (<0,002 mm)	Proctor Max. Density (Ib/ft3)	Proctor Optimum Molature (%)	Ash (%)	USDA Textural Classification	AASHTO	Color	#4 (%)	\$10 (%)	840 (%)	#200 (%)	lows DOT Classification
B-1	0.0	-8.0	BAG	NP	110	HP	0	96	4	6	112	114	T	Sh	A-3(0)	Brown (7.5Y 4/6) Poorty Graded Sand	100	100	80	14	Seed
B-1	-8.0	-15.0	BAG	tip	HP	E/P	0	96	2	2	109	12.7		SA	A-3(0)	Brown (7.5Y 4/3) Poorty Graded Sans	100	100	85	4	Suitaba
B-2	0.0	-8.0	BAG	HP	110	NP	0	95	4	1.	112	11.0		SA	A-3(0)	Brown (7.5YR 5/4) Poorly Graded Band with Silt	100	100	84	5	Select
B-2	-9.0	-	BAG	NP	710	7.02	6	97	2	1	118	7.0	7	SA	A-3(0)	Brown (7.5YR 5/6) Poorly Graded Sand	100	100	85	3	Select
B-2	-20.0		BAG	17	13	4	2. 1	69	25	6	119	12	1	SALO	A-2-4(0)	Gray Brown (7.5YR 4/1) Silty Clarey Sand	100	100	88	31	Sutati
B-3	0.0	-8.0	BAG	NP	NP	NP	0	69	10	1.	112	-11	7	SA	A-2-4(0)	Brown (7.5YR 2.5/2) Poorty Graded Sand with Sit	100	100	86	11	5-clock
B-3	-8.0	-	BAG	HP	NP	NP	0	90	0	1	113	8		SA	A-3(0)	Brown (7.5YR 5/4) Poorty Graded Sand with Sit	100	100	.67	10	Search
B-3	-13.0	-	BAG	MP	NP	HD	0	97			109	13	7		A-3(0)	Brown (7,5YR 5/6) Poorty Graded Sand	100	100	80	3	SHORE
8-3	-19.0	1.4.0	BAG		13	11	1	49	37	14	114	11	7	LO	A-6(2)	Brown (7.5YR 3/1) Sandy Lean Clay	100	99	0.0	51	Sietec

BORING 1



BORING 2



BORING 3

